

Quotation for proposed interiors for Chikkamagaluru District Co-operative Central Bank, Ratnagiri Road, Chikkamagaluru-577101

GROUND FLOOR

S.NO	Description	Unit	QTY	Rate	Amount
1	Reception Table				
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 4mm veneer for exposed surfaces with melamine mat polish (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer), Table top - 38mm thick ply wood, Edges to be finished with PVC edge banding and veneer, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Table	Sqm	1.00	
		Storage	Sqm	1.00	
2	Reception back Panelling				
	Providing and fixing for using 19mm commercial ply finish should be 1 mm laminate, complete as per specifications in Design/Drawing.		Sqm	1.00	
3	Wooden Rafter Panelling				
	Providing and fixing pvc Rafter for using 12mm ply for panelling works and fixing pvc rafter exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.		Sqm	1.00	
			Sqm	1.00	
4	Aluminium frame wood partition				
	Low Hight Partition Providing and fixing of 75mm thick partition of 1350mm height 50X50mm aluminium Frame with both side 12mm commercial ply partition finish should be 1 mm laminate, All joints should be 4mm groove. and fixed 8mm frosted glass, complete as per specifications in Design/Drawing.		Sqm	1.00	
	Full Hight Partition Providing and fixing of 75mm thick partition of 3450mm height 50X50mm aluminium Frame with both side 12mm commercial ply partition finish should be 1 mm laminate, All joints should be 4mm groove. and fixed 8mm frosted glass, complete as per specifications in Design/Drawing .		Sqm	1.00	

S.NO	Description		Unit	QTY	Rate	Amount
5	Glass Door					
	Providing and fixing Frameless glass door with 12mm toughened glass with necessary patch fittings (Ozone or equivalent) of approved make and as per the directions of the client / architect complete as per Design/Drawing.		Sqm	1.00		
6	Grass wall					
	Providing and fixing pvc Grass wall of approved make and as per the directions of the client / architect complete as per Design/Drawing. REF-CDCC/GF-1/REC/WALL		Sqm	1.00		
7	Wood with Glass Doors					
	Providing and fixing of 30mm thick of 2100mm height wooden Door, both side 1 mm laminate, (selected by the client / Architect) fixed 8mm frosted glass, including necessary hardware's, complete as per specifications in Design/Drawing.		No's	1.00		
8	M D Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 4mm veneer for exposed surfaces with melamine mat polish (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding and veneer, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing. REF-CDCC/GF-1/MDT	Table	Sqm	1.00		
		Storage	Sqm	1.00		
9	Wall Panelling M D ROOM					
	Providing and fixing for using 12mm commercial ply finish should be 4mm veneer for exposed surfaces with melamine mat polish, complete as per specifications in Design/Drawing.		Sqm	1.00		
10	M D ROOM Wooden Rafter Panelling					
	Providing and fixing pvc Rafter for using 12mm ply for panelling works and fixing pvc rafter exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.		Sqm	1.00		
11	FILE STORAGE M D ROOM					
	Providing and fixing FILE STORAGE using 18mm ply for frame works and 19mm premium blockboards for shutters, with .8mm white laminate for inside surfaces and 1mm		Sqm	1.00		

S.NO	Description		Unit	QTY	Rate	Amount
	laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per		Sqm	1.00		
12	Manager Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 4mm veneer for exposed surfaces with melamine mat polish (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding and veneer, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing. REF-CDCC/TYP-1/MT	Table	Sqm	1.00		
		Storage	Sqm	1.00		
13	WALL FILE STORAGE Manager					
	Providing and fixing FILE STORAGE using 18mm ply for frame works and 19mm premium blockboards for shutters, with .8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.		Sqm	1.00		
14	Planning and Development Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Table	Sqm	1.00		
		Storage	Sqm	1.00		
		Table and Storage	Sqm	1.00		
15	INSPECTION AND AUDIT Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding, 8 Module	Table	Sqm	1.00		
		Storage	Sqm	1.00		
		Table and Storage	Sqm	1.00		

S.NO	Description		Unit	QTY	Rate	Amount
	Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	SECRETARY Table and Storage	Sqm	1.00		
16	RECOVERY AND SHG Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Table	Sqm	1.00		
		Storage	Sqm	1.00		
		Table and Storage	Sqm	1.00		
17	LOAN SANCTION Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Table	Sqm	1.00		
		Storage	Sqm	1.00		
		Table and Storage	Sqm	1.00		
18	ACCOUNTS Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Table	Sqm	1.00		
		Storage	Sqm	1.00		
		Table and Storage	Sqm	1.00		
19	Wall Panelling					
	Providing and fixing for using 12mm commercial ply finish should be 1 mm laminate, complete as per specifications in Design/Drawing.		Sqm	1.00		

S.NO	Description		Unit	QTY	Rate	Amount
20	Wood Panelling for Column					
	Providing and fixing of 4 side 19mm commercial ply finish should be 1 mm laminate, All joints should be 4mm groove, complete as per specifications in Design/Drawing.		Sqm	1.00		
21	Chairs					
	Featherlite (HIGH BACK CHAIRS)					
	MD Workstations		No's	1.00		
	Featherlite (TASK SEATING)					
	Manager Workstations		No's	1.00		
	Waiting Chairs SS		No's	1.00		
	Featherlite (VISITOR CHAIRS)		No's	1.00		
	2 seater Sofa		No's	1.00		
	3 seater Sofa		No's	1.00		
	Sofa come bed		No's	1.00		
22	Rolling Blinds		No's	1.00		
23	FALSE CEILING					
	Providing and fixing of Wooden False Ceiling 12mm thick ply with fixing 4mm veneer for exposed surfaces with melamine mat polish with necessary GI Channels, Hardware's complete as per Design/Drawing.		Sqm	1.00		
FRIST FLOOR						
24	Wooden Rafter Panelling for entrance					
	Providing and fixing pvc Rafter for using 12mm ply for panelling works and fixing pvc rafter exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.		Sqm	1.00		
			Sqm	1.00		
25	PRESIDENT Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 4mm veneer for exposed surfaces with melamine mat polish (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer), Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding and veneer, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Table	Sqm	1.00		
	REF-CDCC/FF-1/PRT	Storage	Sqm	1.00		

S.NO	Description		Unit	QTY	Rate	Amount
26	Wall Panelling PRESIDENT ROOM					
	Providing and fixing for using 12mm commercial ply finish should be 4mm veneer for exposed surfaces with melamine mat polish, complete as per specifications in Design/Drawing		Sqm	1.00		
27	PRESIDENT ROOM Wooden Rafter Panelling					
	Providing and fixing pvc Rafter for using 12mm ply for panelling works and fixing pvc rafter exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing .		Sqm	1.00		
			Sqm	1.00		
28	FILE STORAGE PRESIDENT ROOM					
	Providing and fixing FILE STORAGE using 18mm ply for frame works and 19mm premium blockboards for shutters, with .8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.		Sqm	1.00		
29	WOODEN FLOORING PRESIDENT ROOM					
	Providing and fixing WOODEN FLOORING using 6mm ply for floor and fixing of wooden floor for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.		Sqm	1.00		
30	VICE-PRESIDENT Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 4mm veneer for exposed surfaces with melamine mat polish (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding and veneer, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing. REF- CDCC/FF-1/VCT	Table	Sqm	1.00		
		Storage	Sqm	1.00		
31	Wall Panelling VICE-PRESIDENT ROOM					
	Providing and fixing for using 12mm commercial ply finish should be 4mm veneer for exposed surfaces with melamine mat polish, complete as per specifications in Design/Drawing.		Sqm	1.00		

S.NO	Description		Unit	QTY	Rate	Amount
32	VICE-PRESIDENT ROOM Wooden Rafter Panelling					
	Providing and fixing pvc Rafter for using 12mm ply for panelling works and fixing pvc rafter exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.		Sqm	1.00		
33	FILE STORAGE VICE- PRESIDENT ROOM					
	Providing and fixing FILE STORAGE using 18mm ply for frame works and 19mm premium blockboards for shutters, with .8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.		Sqm	1.00		
			Sqm	1.00		
34	FUTURE DEVELOPMENT Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Table	Sqm	1.00		
		Storage	Sqm	1.00		
		Table and Storage	Sqm	1.00		
		SECRETARY Table and Storage	Sqm	1.00		
35	FUTURE MANAGER Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Table	Sqm	1.00		
		Storage	Sqm	1.00		
36	WALL FILE STORAGE Manager					

S.NO	Description		Unit	QTY	Rate	Amount
	Providing and fixing FILE STORAGE using 18mm ply for frame works and 19mm premium blockboards for shutters, with .8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.		Sqm	1.00		
37	Manager Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Table	Sqm	1.00		
		Storage	Sqm	1.00		
38	WALL FILE STORAGE Manager					
	Providing and fixing FILE STORAGE using 18mm ply for frame works and 19mm premium blockboards for shutters, with .8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.		Sqm	1.00		
39	ESD DEPT. Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Table	Sqm	1.00		
		Storage	Sqm	1.00		
		Table and Storage	Sqm	1.00		
40	SECRETARY Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood,	Table	Sqm	1.00		

S.NO	Description		Unit	QTY	Rate	Amount
	Edges to be finished with PVC edge banding, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Storage	Sqm	1.00		
41	CONFERENCE Workstations					
	Providing and making Ply wood Manager Workstations using 19mm commercial plywood, with 0.8mm white laminate for inside surfaces and 4mm veneer for exposed surfaces with melamine mat polish (selected by the client / Architect) including necessary hardware's including Side partitions, Storage unit (includes 2-3 drawer),Table top - 25 mm thick ply wood, Edges to be finished with PVC edge banding and veneer, 8 Module Switch socket (Data & voice) below table top per workstation and Wire manager - ABS plastic grommet one number per table, complete as per specifications in Design/Drawing.	Table	Sqm	1.00		
		Table	Sqm	1.00		
42	Wall Panelling CONFERENCE ROOM					
	Providing and fixing for using 12mm commercial ply finish should be 4mm veneer for exposed surfaces with melamine mat polish, complete as per specifications in Design/Drawing		Sqm	1.00		
43	PROJECTOR UNIT					
	Providing and fixing DRAWER STORAGE using 18mm ply for frame works and 19mm premium blockboards for shutters, with .8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.		Sqm	1.00		
	PROJECTOR UNIT back Panelling					
	Providing and fixing for using 19mm commercial ply finish should be 1 mm laminate, complete as per specifications in Design/Drawing.		Sqm	1.00		
	Inlight Motorised Home Theatre Projector Screen 8 Ft x 4.5 Ft – 106 Inches Diagonal, 16:9 Format, Full HD 1080P-3D-4K Ready(White)		No's	1.00		
	Epson EB-X49 XGA Projector Brightness: 3600lm with HDMI Port (Optional Wi-Fi) (V11H982040)		No's	1.00		
44	FILE STORAGE CONFERENCE ROOM					

S.NO	Description	Unit	QTY	Rate	Amount
	Providing and fixing FILE STORAGE using 18mm ply for frame works and 19mm premium blockboards for shutters, with .8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.	Sqm	1.00		
45	WOODEN FLOORING CONFERENCE ROOM				
	Providing and fixing WOODEN FLOORING using 6mm ply for floor and fixing of wooden floor for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.	Sqm	1.00		
46	Chairs				
	Featherlite (HIGH BACK CHAIRS)				
	VICE-PRESIDENT	No's	1.00		
	PRESIDENT	No's	1.00		
	FUTURE MANAGER	No's	1.00		
	Manager Workstations	No's	1.00		
	Featherlite (TASK SEATING)	No's	1.00		
	FUTURE DEVELOPMENT , ESD DEPT, SECRETARY	No's	1.00		
	Waiting Chairs SS	No's	1.00		
	Featherlite (VISITOR CHAIRS)	No's	1.00		
	2 seater Sofa	No's	1.00		
	3 seater Sofa	No's	1.00		
	Sofa come bed	No's	1.00		
47	Rolling Blinds	No's	1.00		
48	Aluminium frame wood partition				
	Low Hight Partition Providing and fixing of 75mm thick partition of 1350mm height 50X50mm aluminium Frame with both side 12mm commercial ply partition finish should be 1 mm laminate, All joints should be 4mm groove. and fixed 8mm frosted glass, complete as per specifications in Design/Drawing.	Sqm	1.00		

S.NO	Description	Unit	QTY	Rate	Amount
	Full Hight Partition Providing and fixing of 75mm thick partition of 3450mm height 50X50mm aluminium Frame with both side 12mm commercial ply partition finish should be 1 mm laminate, All joints should be 4mm groove. and fixed 8mm frosted glass, complete as per specifications in Design/Drawing .	Sqm	1.00		
	PRESIDENT AND VICE-PRESIDENT Full Hight Partition Providing and fixing of 75mm thick partition of 3000mm height 50X50mm aluminium Frame with both side 12mm commercial ply partition finish should be 4mm veneer for exposed surfaces with melamine mat polish , All joints should be 4mm groove. and fixed 8mm frosted glass, complete as per specifications in Design/Drawing. NOTE The aluminium frame should be fixed up to the ceiling and the 12mm ply should be fixed till 3450mm.	Sqm	1.00		
	CONFERENCE Full Hight Partition Providing and fixing of 75mm thick partition of 3450mm height 50X50mm aluminium Frame with both side 12mm commercial ply partition finish should be 4mm veneer for exposed surfaces with melamine mat polish , All joints should be 4mm groove. and fixed 8mm frosted glass, complete as per specifications in Design/Drawing NOTE The aluminium frame should be fixed up to the ceiling and the 12mm ply should be fixed till 3450mm	Sqm	1.00		
49	FALSE CEILING				
	Providing and fixing of Wooden False Ceiling 12mm thick ply with fixing 4mm veneer for exposed surfaces with melamine mat polish with necessary GI Channels, Hardware's complete as per Design/Drawing.	Sqm	1.00		
		Sqm	1.00		
50	Wood Panelling for Column				
	Providing and fixing of 4 side 19mm commercial ply finish should be 1 mm laminate, All joints should be 4mm groove, complete as per specifications in Design/Drawing.	Sqm	1.00		
51	Wood with Glass Doors				

S.NO	Description	Unit	QTY	Rate	Amount
	Providing and fixing of 30mm thick of 2100mm height wooden Door, both side 1 mm laminate, (selected by the client / Architect) fixed 8mm frosted glass, including necessary hardware's, complete as per specifications in Design/Drawing.	No's	1.00		
SECOND FLOOR					
51	Wall Panelling MULTI-PURPOSE HALL				
	Providing and fixing for using 12mm commercial ply finish should be 4mm veneer for exposed surfaces with melamine mat polish, complete as per specifications in Design/Drawing.	Sqm	1.00		
52	QUEEN SIZE COT for rooms				
	Providing and fixing WARDROBE using 18mm ply for frame works and 19mm premium blockboards for TOP, with .8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.	Sqm	1.00		
53	SINGLE SIZE COT for rooms				
	Providing and fixing WARDROBE using 18mm ply for frame works and 19mm premium blockboards for TOP, with .8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.	Sqm	1.00		
54	WARD ROBE				
	Providing and fixing WARDROBE using 18mm ply for frame works and 19mm premium blockboards for shutters, with .8mm white laminate for inside surfaces and 1mm laminate for exposed surfaces (selected by the client / Architect) including necessary hardware's complete as per Design/Drawing.	Sqm	1.00		
55	TV UNIT	Sqm	1.00		
THIRD FLOOR					
56	Wall Panelling MULTI-PURPOSE HALL				
	Providing and fixing for using 12mm commercial ply finish should be 4mm veneer for exposed surfaces with melamine mat polish, complete as per specifications in Design/Drawing.	Sqm	1.00		
57	Wood Panelling for Column				
	Providing and fixing of 4 side 19mm commercial ply finish should be 1 mm laminate, All joints should be 4mm groove, complete as per specifications in Design/Drawing.	Sqm	1.00		

S.NO	Description	Unit	QTY	Rate	Amount
58	FALSE CEILING				
	Providing and fixing of Wooden False Ceiling 12mm thick ply with fixing 4mm veneer for exposed surfaces with melamine mat polish with necessary GI Channels, Hardware's complete as per Design/Drawing.	Sqm	1.00		
59	STAGE				
	Providing and fixing of STAGE with 450 MM height with 75MM X 75 MM M.S pipe @ 1.00 mtr C/C both vertical & horizontal , with vertical 75MM X 75 MM M.S pipe support , top & sides with 18MM + 18mm (double) commercial ply board fixed, with 8MM engineerd wooden flooring,	Sqm	1.00		
60	Metal Chair with with cushion covered	No	1.00		